**SECURE MISSION SOLUTIONS**

# Volume 1: Technical Approach

## RFP SOL-DC-12-00025 HSPD-12 PACS Maintenance for NEIC

Submitted: December 31, 2012
Submitted to:
Ms. Esther Kim; kim.esther@epa.gov
U.S. Environmental Protection Agency
Administrative Contract Service Center
Mail Code: 3803R
1200 Pennsylvania Avenue, NW
Washington, DC 20460


Submitted by:
Secure Mission Solutions, LLC.
8260 Willow Oaks Corporate Drive, Suite 300
Fairfax, VA 22031
Voice: (703) 245-1300
Fax: (703) 245-1362
DUNS: (b)(4)



| SMS Contact Information | | | | |
|---|---|---|---|---|
| | (b)(4) | Director of Contracts | | |
| | (703) (b)(4) | | (b)(4) | @securemissionsolutions.com |
| | (b)(4) | Director Critical Asset Protection Division | | |
| | (703) (b)(4) | | (b)(4) | @securemissionsolutions.com |


No exceptions taken.

Authorized signature:
(b)(4)

(b)(4), Director of Contracts


*For Official Use Only and Solicitation Sensitive*

*This proposal includes data that shall not be disclosed outside the Government and shall not be duplicated, used, or disclosed-in whole or in part-for any purpose other than to evaluate this proposal. If, however, a task order is awarded to this offeror as a result of-or in connection with-the submission of this data, the Government shall have the right to duplicate, use, or disclose the data to the extent provided in the resulting task order. This restriction does not limit the Government's right to use information contained in this data if obtained from another source without restriction. The data subject to this restriction are contained in all pages of this proposal.*

December 31, 2012

Esther Kim, Contracting Specialist
U.S. Environmental Protection Agency
Administrative Contract Service Center
Mail Code: 3803R
1200 Pennsylvania Avenue, NW
Washington, DC 20460

Subject: **SOL-DC-12-00025**

Dear Ms. Kim:
Secure Mission Solutions LLC (SMS) is pleased to provide our proposal in response to Solicitation No. **SOL-DC-12-00025**. Our submission includes three volumes per the RFP comprised of 24 electronic files (see table below), submitted before 10:00 am on December 31, 2012.

| Requirement | File Name | File type |
|---|---|---|
| Volume I: Technical Approach | Vol 1_Technical Approach_SMS_SOL-DC-12-00025 | PDF (1) |
| | Vol 1_Appendix H: TOC for Attachments 1 – 17, Attachments 1 – 17 | PDFs (18) |
| | Vol 1_Appendix I: Attachment 18 | PDF (1) |
| Volume II: Experience & Past Performance | Vol 2_Experience and Past Performance_SMS_SOL-DC-12-00025 | PDF (1) |
| Volume III: Price | Vol 3_Tab A_Price Schedule_SMS_SOL-DC-12-00025 | PDF (1) |
| | Vol 3_Tab B_SF 1449 and SF 30 (signed) | PDF (1) |
| | Vol 3_Tab C_Representations and Certifications_SMS_SOL-DC-12-00025 | PDF (1) |

SMS has also ensured that our four past performance questionnaires have been submitted to EPA by our references. The proposal acceptance period is valid for 90 days.

Should you have any questions, or require anything further, please contact me at either (703)(b)(4) or at(b)(4)@securemissionsolutions.com

Sincerely,
(b)(4)

(b)(4) Director of Contracts

| Page Count Summary | |
|---|---|
| Cover Page | 1 |
| Letter of Submission | 1 |
| Table of Contents | NA |
| Sections 1 through 7 | 31 |
| Appendixes | NA |
| Total page count | 33 |

# TABLE OF CONTENTS

**1.0 TASK AREA 1- PROJECT PREPARATION & MANAGEMENT ..... 1**

1.1 TASK AREA 1 INTRODUCTION ..... 1
1.2 SUBTASK 1: BUSINESS LICENSES, CERTIFICATES OF INSURANCE AND CLARIFICATIONS AND EXCLUSIONS ..... 2
1.3 SUBTASK 2: PROJECT PERSONNEL ..... 2
1.4 WORK SEQUENCE ..... 3
*1.4.1 Project Mobilization ..... 3*
*1.4.2 Roles and Responsibilities ..... 5*
*1.4.3 Installation Approach [SOW 4.1.4, 4.1.8] ..... 5*
*1.4.4 Parallel Efforts ..... 6*
1.5 SUBCONTRACTOR ON-SITE PROCEDURES AND SCOPE OF WORK ..... 7
1.6 CABLE MANAGEMENT FOR SECURITY SYSTEM EQUIPMENT INSTALLATION ..... 7
1.7 ADDITIONAL POWER OR UPS INSTALLATION ..... 8
1.8 INVENTORY CONTROL PROCEDURES FOR NEW EQUIPMENT AND SPARE PARTS [SOW 4.1.1, 4.1.2] ..... 8
1.9 TESTING PROCEDURES [SOW 4.1.5] ..... 9
*1.9. 1 Testing Overview ..... 9*
*1.9.2 Performance Verification Test (PVT) ..... 9*
*1.9.3 Endurance Test (ET) ..... 9*
*1.9.4 Final Acceptance Test (FAT) ..... 10*
1.10 SECURITY TESTING & EVALUATION [SOW 4.1.6] ..... 10
1.11 RISK MANAGEMENT PLAN ..... 11
1.12 STAKEHOLDER MANAGEMENT AND COMMUNICATION PLAN ..... 11
1.13 SECURITY SYSTEMS TRAINING [SOW 4.1.9] ..... 12
1.14 CONTRACT DELIVERABLES [SOW 4.1.10, SOW ATTACHMENT 1] ..... 12

**2.0 TASK AREA 2: HSPD-12 PACS INSTALLATION AND TECHNICAL CAPABILITY ..... 15**

2.1 TASK AREA 2 INTRODUCTION ..... 15
2.2 PACS - ONE AND TWO POTOMAC YARD [SOW 4.2.1] ..... 16
2.3 EAST BUILDING [SOW 4.2.2] ..... 17
*2.3.1 Access Control ..... 17*
*2.3.2 IDS Keypads ..... 17*
*2.3.3 Intrusion Detection ..... 17*
*2.3.4 Duress Button ..... 17*
2.4 WEST BUILDING AND CONNECTING WING [SOW 4.2.2] ..... 17
*2.4.1 Access Control ..... 17*
*2.4.2 IDS Keypads ..... 18*
*2.4.3 Intrusion Detection ..... 18*
*2.4.4 Duress Buttons ..... 18*
2.5 ARIEL RIOS SOUTH [SOW 4.2.3] ..... 18
*2.5.1 Access Control ..... 18*
*2.5.2 Intrusion Detection ..... 18*
*2.5.3 Duress Buttons ..... 19*
2.6 ARIEL RIOS NORTH [SOW 4.2.3] ..... 19
*2.6.1 Access Control ..... 19*
*2.6.2 IDS Keypads ..... 19*
*2.6.3 Intrusion Detection ..... 19*
*2.6.4 Duress Buttons ..... 19*
2.7 RONALD REAGAN BUILDING [SOW 4.2.4] ..... 20
*2.7.1 Access Control ..... 20*
*2.7.2 IDS Keypads ..... 20*
*2.7.3 Intrusion Detection ..... 20*
*2.7.4 Duress Buttons ..... 20*
2.8 L STREET BUILDING [SOW 4.2.5] ..... 20

Use or disclosure of data on this sheet is subject to the restriction on the title page of this proposal.

*2.8.1 Access Control* ..... *20*
*2.8.2 Intrusion Detection* ..... *21*
*2.8.3 IDS Keypad* ..... *21*
2.9 V STREET BUILDING [SOW 4.2.6] ..... 21
*2.9.1 Access Control* ..... *21*
*2.9.2 IDS Keypad* ..... *21*
*2.9.3 Intrusion Detection* ..... *21*
2.10 PACS VIRTUAL SERVER CONFIGURATION [SOW 4.2.7] ..... 21
2.11 PACS VIRTUAL SERVER REQUIREMENTS [SOW 4.2.8] ..... 22
2.12 PACS WORKSTATION CONFIGURATION [SOW 4.2.9] ..... 22
2.13 PACS WORKSTATIONS AND PRINTER REQUIREMENT [SOW 4.2. 10] ..... 22
2.14 PACS ENROLLMENT/BADGING CLIENTS [SOW 4.2. 11]] ..... 22
2.15 VISITOR MANAGEMENT SYSTEM [SOW 4.2.12, SUBTASK 5] ..... 23
2.16 ONLINE CERTIFICATE STATUS PROTOCOL SOFTWARE (OCSP) [SOW 4.2.13] ..... 24
2.17 REQUIRED PACS FUNCTIONALITY [SOW 4.2.14] ..... 24
2.18 COMPREHENSIVE SCHEDULE ..... 24

**3.0 TASK AREA 3: INTRUSION DETECTION SYSTEMS [SOW 4.3] ..... 25**

3.1 OVERVIEW OF REQUIREMENTS [SOW 4.3.1, 4.3.2] ..... 25
3.2 IDS CONTROL PANEL [SOW 4.3.9] ..... 25
3.3 IDS KEYPADS [SOW 4.3.10] ..... 25
3.4 SENSORS/GLASS-BREAKS [SOW 4.3.11] ..... 25
3.5 DOOR POSITION SWITCHES [SOW 4.3.12] ..... 26
3.6 MOTION DETECTOR SENSORS [SOW 4.3.13] ..... 26
3.7 DURESS BUTTONS [SOW 4.3.14] ..... 26
3.8 STROBE [SOW 4.3.15] ..... 26

**4.0 TASK AREA 4: MAINTENANCE ..... 26**

4.1 SERVICE & MAINTENANCE FOR EPA LOCATIONS [SOW TASK 4-A, 1.3] ..... 26
4.2 MAINTENANCE FOR OPTION YEARS [SOW TASK 4-B] ..... 26
4.3 PACS HARDWARE MAINTENANCE AND SOFTWARE LICENSE SUPPORT [SOW TASK 4-C] ..... 26
4.4 SERVICE/TECHNICAL MAINTENANCE SUPPORT [SOW TASK 4-D, E, F, G] ..... 27
4.5 FIELD CHANGES/SOFTWARE MODIFICATIONS [SOW TASK 4-H] ..... 27
4.6 PREVENTATIVE MAINTENANCE [SOW TASK 4-I, J, K, L, N] ..... 27
4.7 MAINTENANCE CHECKLISTS & LOGS [SOW TASK 4-M, O, P] ..... 27
4.8 PACS DATABASE CONFIGURATION [SOW TASK 4-Q] ..... 27
4.9 QUALIFICATIONS OF MAINTENANCE PERSONNEL [SOW TASK 4-R, EVALUATION FACTOR 2-SUBFACTOR 3] 28

**5.0 TASK AREA 5: OPTIONAL ..... 28**

5.1 TURNSTILES OPTICAL TURNSTILES – BARRIER STYLE [SOW 4.4] ..... 28
5.2 ADDITIONAL INSTALLATION LABOR [SOW 4.5] ..... 28

**6.0 GENERAL COMPLIANCE ..... 28**

6.1 MEETINGS ..... 28
6.2 SECURITY CLEARANCES ..... 28
6.3 STATUS REPORTS ..... 28
6.4 SAFETY ..... 29
6.5 INFORMATION ASSURANCE (IA) REQUIREMENTS ..... 29
6.6 SITE/USER SPECIFIC REQUIREMENTS ..... 29
*6.6.1 Protection of Government Property* ..... *29*
*6.6.2 Work Area Requirements* ..... *30*

**7.0 QUALITY ASSURANCE ..... 30**

**APPENDIX A: BUSINESS LICENSES ..... I**

**APPENDIX B: CERTIFICATE OF INSURANCE ..... 1**

Use or disclosure of data on this sheet is subject to the restriction on the title page of this proposal.

**APPENDIX C: CORPORATE CERTIFICATIONS** ..... 1

C-1: SMS GSA HSPD-12 LETTER ..... 1
C-2: SMS GSA HSPD-12 CERTIFICATION ..... 2
C-3: SMS AMAG LETTER ..... 3
C-4: SMS MDI CERTIFIED REPRESENTATIVE ..... 4
C-5: SMS PELCO CERTIFIED REPRESENTATIVE ..... 5

**APPENDIX D: RESUMES** ..... 11

D.1: (b)(4), PROJECT DIRECTOR (KEY) ..... 11
D.2: (b)(4), PROJECT MANAGER ..... 13
D.3: (b)(4) PROJECT ENGINEER ..... 15
D.4: (b)(4) PROJECT SUPERINTENDENT ..... 17
D.5: (b)(4) ENGINEER/SERVICE MANAGER ..... 0

**APPENDIX E: PERSONNEL CERTIFICATIONS** ..... 1

E.1: (b)(4) CERTIFICATION: MDI SAFENET ..... 1
E.2: CERTIFICATION: AMAG SECURITY MANAGEMENT SYSTEM ..... 2

**APPENDIX F: SMS EPA ESS PROJECT ORGANIZATIONAL CHART** ..... 1

**APPENDIX G: DRAFT PROJECT SCHEDULE** ..... 1

**APPENDIX H: ATTACHMENTS 1-17: DESIGN RISER/BLOCK DIAGRAMS & EQUIPMENT LIST** [SUBTASK 1]; DOOR/ROOM SCHEDULE, STANDARD DOOR CONFIGURATION AND CABLING [SUBTASK 3]; AND STANDBY BATTERY AND EXTERNAL POWER SUPPLY CALCULATIONS [SUBTASK 4] ..... 1

**APPENDIX I: ATTACHMENT 18: MANUFACTURER PRODUCT/EQUIPMENT CUT SHEETS [SUBTASK 2]** ..... 1

**APPENDIX J: NON-KEY PERSONNEL CERTIFICATIONS** ..... 1

J-1: (b)(4) AMAG SECURITY MANAGEMENT SYSTEM CERTIFICATION ..... 1
J-2: STARWATCH CERTIFICATION ..... 2
J-3: VERINT CERTIFICATION ..... 3
J-4: UNICAM CERTIFICATION ..... 4
J-5: BOSCH RPS 5.7 CERTIFICATION ..... 5
J-6: BOSCH GV2 CONTROL COMMUNICATOR CERTIFICATION ..... 6
J-7: (b)(4) AMAG CERTIFICATION ..... 7
J-8: (b)(4) AMAG CERTIFICATION ..... 8
J-9: (b)(4) AMAG CERTIFICATION ..... 9
J-10: (b)(4) AMAG CERTIFICATION ..... 10
J-11: (b)(4) CERTIFICATION: PELCO ..... 11

## TABLE OF CONTENTS ATTACHMENTS 1-17 (APPENDIX H)

DESIGN RISER/BLOCK DIAGRAMS & EQUIPMENT LIST [SUBTASK 1]; DOOR/ROOM SCHEDULE, STANDARD DOOR CONFIGURATION AND CABLING [SUBTASK 3]; AND STANDBY BATTERY AND EXTERNAL POWER SUPPLY CALCULATIONS [SUBTASK 4]


| ATTACHMENT | TITLE | PAGE(S) |
|---|---|---|
| | ROOM B223 RISERS | 1-2 |
| | ROOM 1224 RISERS | 3-4 |
| | ROOM 3230 &4220 RISERS | 5 |
| | ROOM 4423A RISERS | 6 |
| | ROOM 4423B RISERS | 7 |
| | ROOM 5110 RISERS | 8 |
| | ROOM 5224 RISERS | 9 |
| | ROOM 5423A RISERS | 10 |
| | ROOM 5423B RISERS | 11 |
| | ROOM 6223A RISERS | 12 |
| | ROOM 6223B RISERS | 13 |
| | ROOM 6224 RISERS | 14 |
| | ROOM 6431A RISERS | 15 |
| | ROOM 6431B RISERS | 16 |
| | ROOM 6431C RISERS | 17 |
| | ROOM B223 DOOR SCHEDULE | 1 |
| | ROOM B223 BATTERY CALCULATION | 2-4 |
| | ROOM 1224 DOOR SCHEDULE | 5-6 |
| | ROOM 1224 BATTERY CALCULATION | 7-9 |
| | ROOM 3230 &4220 DOOR SCHEDULE | 10 |
| | ROOM 3230 &4220BATTERY CALCULATION | 11-13 |
| | ROOM 4423A DOOR SCHEDULE | 14 |
| | ROOM 4423A BATTERY CALCULATION | 15-17 |
| | ROOM 4423B DOOR SCHEDULE | 18 |
| | ROOM 4423B BATTERY CALCULATION | 19 |
| | ROOM 5110 DOOR SCHEDULE | 20 |
| | ROOM 5110 BATTERY CALCULATION | 21-22 |
| | ROOM 5224 DOOR SCHEDULE | 23 |
| | ROOM 5224 BATTERY CALCULATION | 24-25 |
| | ROOM 5423A DOOR SCHEDULE | 26 |
| | ROOM 5423A BATTERY CALCULATION | 27-29 |
| | ROOM 5423B DOOR SCHEDULE | 30 |
| | ROOM 5423B BATTERY CALCULATION | 31-32 |
| | ROOM 6223A DOOR SCHEDULE | 33 |
| | ROOM 6223A BATTERY CALCULATION | 34-36 |
| | ROOM 6223B DOOR SCHEDULE | 37 |
| | ROOM 6223B BATTERY CALCULATION | 38-40 |
| | ROOM 6224 DOOR SCHEDULE | 41 |
| | ROOM 6224 BATTERY CALCULATION | 42 |
| | ROOM 6431A DOOR SCHEDULE | 43 |
| | ROOM 6431A BATTERY CALCULATION | 44-46 |
| | ROOM 6431B DOOR SCHEDULE | 47 |
| | ROOM 6431B BATTERY CALCULATION | 48 |
| | ROOM 6431C DOOR SCHEDULE | 49 |
| | ROOM 6431C BATTERY CALCULATION | 50-52 |
| | EAST BUILDING EQUIPMENT LIST TOTAL COUNTS | 53 |


Use or disclosure of data on this sheet is subject to the restriction on the title page of this proposal.

## TABLE OF CONTENTS ATTACHMENTS 1-17 (APPENDIX H)

DESIGN RISER/BLOCK DIAGRAMS & EQUIPMENT LIST [SUBTASK 1]; DOOR/ROOM SCHEDULE, STANDARD DOOR CONFIGURATION AND CABLING [SUBTASK 3]; AND STANDBY BATTERY AND EXTERNAL POWER SUPPLY CALCULATIONS [SUBTASK 4]


| ATTACHMENT | TITLE | PAGE(S) |
|---|---|---|
| | L-STREET RISERS | 1-3 |
| | L-STREET DOOR SCHEDULE | 1 |
| | L-STREET BATTERY CALCULATION | 2-4 |
| | L-STREET (2) DOOR SCHEDULE | 5 |
| | L-STREET (2) BATTERY CALCULATION | 6-8 |
| | L-STREET (3) DOOR SCHEDULE | 9 |
| | L-STREET (3) BATTERY CALCULATION | 10 |
| | L-STREET EQUIPMENT LIST TOTAL COUNTS | 11 |
| | ROOM 1323A RISERS | 1 |
| | ROOM 1421A (2) RISERS | 2 |
| | ROOM 1421A RISERS | 3 |
| | ROOM 1525 RISERS | 4 |
| | ROOM 3423 RISERS | 5 |
| | ROOM 3525 RISERS | 6 |
| | ROOM 5525 RISERS | 7 |
| | ROOM 6525 RISERS | 8 |
| | ROOM 7525 RISERS | 9 |
| | ROOM EOC RISERS | 10 |
| | ROOM 1323A DOOR SCHEDULE | 1 |
| | ROOM 1323A BATTERY CALCULATION | 2-3 |
| | ROOM 1421A DOOR SCHEDULE | 4 |
| | ROOM 1421A BATTERY CALCULATION | 5 |
| | ROOM 1421A (2) DOOR SCHEDULE | 6 |
| | ROOM 1421A (2) BATTERY CALCULATION | 7-8 |
| | ROOM 1525 DOOR SCHEDULE | 9 |
| | ROOM 1525 BATTERY CALCULATION | 10 |
| | ROOM 3423 DOOR SCHEDULE | 11 |
| | ROOM 3423 BATTERY CALCULATION | 12 |
| | ROOM 3525 DOOR SCHEDULE | 13 |
| | ROOM 3525 BATTERY CALCULATION | 14 |
| | ROOM 5525 DOOR SCHEDULE | 15 |
| | ROOM 5525 BATTERY CALCULATION | 16-18 |
| | ROOM 6525 DOOR SCHEDULE | 19 |
| | ROOM 6525 BATTERY CALCULATION | 20-21 |
| | ROOM 7525 DOOR SCHEDULE | 22 |
| | ROOM 7525 BATTERY CALCULATION | 23 |
| | ROOM EOC DOOR SCHEDULE | 24 |
| | ROOM EOC BATTERY CALCULATION | 25 |
| | ARIEL RIOS NORTH BUILDING EQUIPMENT LIST TOTAL COUNTS | 26 |
| | OVERVIEW AMAG SYSTEM CONFIGURATION FOR ACCESS CONTROL STATIONS | 1-4 |

## TABLE OF CONTENTS ATTACHMENTS 1-17 (APPENDIX H)

DESIGN RISER/BLOCK DIAGRAMS & EQUIPMENT LIST [SUBTASK 1]; DOOR/ROOM SCHEDULE, STANDARD DOOR CONFIGURATION AND CABLING [SUBTASK 3]; AND STANDBY BATTERY AND EXTERNAL POWER SUPPLY CALCULATIONS [SUBTASK 4]


| ATTACHMENT | TITLE | PAGE(S) |
|---|---|---|
| | POTOMAC YARD RISERS | 1 |
| | POTOMAC YARD DOOR SCHEDULE | 1 |
| | POTOMAC YARD BATTERY CALCULATIONS | 2 |
| | ROOM B-1 LAN RISERS | 1 |
| | ROOM B-3 LAN RISERS | 1 |
| | CONCOURSE TS RISERS | 2 |
| | ROOM M-1200 RISERS | 2 |
| | ROOM FMSD RISERS | 3 |
| | ROOM FMSD (2) RISERS | 4 |
| | ROOM 3RD LAN RISERS | 5-6 |
| | ROOM 6TH LAN RISERS | 7-8 |
| | ROOM 7TH LAN RISERS | 9 |
| | ROOM 8TH LAN RISERS | 9 |
| | ROOM 9TH LAN RISERS | 10 |
| | ROOM B-1 LAN DOOR SCHEDULE | 1 |
| | ROOM B-1 LAN BATTERY CALCULATION | 2-3 |
| | ROOM B-3 LAN DOOR SCHEDULE | 4 |
| | ROOM B-3 LAN BATTERY CALCULATION | 5-6 |
| | CONCOURSE TS DOOR SCHEDULE | 7 |
| | CONCOURSE TS BATTERY CALCULATION | 8-9 |
| | ROOM M-1200 DOOR SCHEDULE | 10 |
| | ROOM M-1200 BATTERY CALCULATION | 11-12 |
| | ROOM FMSD DOOR SCHEDULE | 13 |
| | ROOM FMSD BATTERY CALCULATION | 14-17 |
| | ROOM FMSD (2) DOOR SCHEDULE | 18 |
| | ROOM FMSD (2) BATTERY CALCULATION | 19 |
| | ROOM 3RD LAN DOOR SCHEDULE | 20 |
| | ROOM 3RD LAN BATTERY CALCULATION | 21-23 |
| | ROOM 3RD LAN (2) DOOR SCHEDULE | 24 |
| | ROOM 3RD LAN (2) BATTERY CALCULATION | 25-26 |
| | ROOM 6TH LAN DOOR SCHEDULE | 27 |
| | ROOM 6TH LAN BATTERY CALCULATION | 28-30 |
| | ROOM 6TH LAN (2) DOOR SCHEDULE | 31 |
| | ROOM 6TH LAN (2) BATTERY CALCULATION | 32-33 |
| | ROOM 7TH LAN DOOR SCHEDULE | 34 |
| | ROOM 7TH LAN BATTERY CALCULATION | 35-36 |
| | ROOM 8TH LAN (2) DOOR SCHEDULE | 37 |
| | ROOM 8TH LAN (2) BATTERY CALCULATION | 38-39 |
| | ROOM 9TH LAN DOOR SCHEDULE | 40 |
| | ROOM 9TH LAN BATTERY CALCULATION | 41-42 |
| | RONALD REAGAN EQUIPMENT LIST TOTAL COUNTS | 43 |
| | ROOM 1525 RISERS | 1-2 |
| | ROOM 4138A RISERS | 3 |
| | ROOM 4107 RISERS | 4 |
| | ROOM 4220B RISERS | 5 |

## TABLE OF CONTENTS ATTACHMENTS 1-17 (APPENDIX H)

DESIGN RISER/BLOCK DIAGRAMS & EQUIPMENT LIST [SUBTASK 1]; DOOR/ROOM SCHEDULE, STANDARD DOOR CONFIGURATION AND CABLING [SUBTASK 3]; AND STANDBY BATTERY AND EXTERNAL POWER SUPPLY CALCULATIONS [SUBTASK 4]


| ATTACHMENT | TITLE | PAGE(S) |
|---|---|---|
| | ROOM 1525 DOOR SCHEDULE | 1-2 |
| | ROOM 1525 BATTERY CALCULATION | 3-4 |
| | ROOM 4138A DOOR SCHEDULE | 5 |
| | ROOM 4138A BATTERY CALCULATION | 6-7 |
| | ROOM 4107 DOOR SCHEDULE | 8 |
| | ROOM 4107 BATTERY CALCULATION | 9-10 |
| | ROOM 4220B DOOR SCHEDULE | 11 |
| | ROOM 4220B BATTERY CALCULATION | 12-15 |
| | ARIEL RIOS SOUTH BUILDING EQUIPMENT LIST TOTAL COUNTS | 16 |
| | 3025 V STREET RISERS | 1 |
| | 3025 V STREET BUILDING DOOR SCHEDULE | 1 |
| | 3025 V STREET BUILDING BATTERY CALCULATIONS | 2-3 |
| | 3025 V STREET BUILDING EQUIPMENT LIST TOTAL COUNTS | 4 |
| | ROOM B341 RISERS | 1 |
| | ROOM B411 RISERS | 2 |
| | ROOM 1409 RISERS | 3-4 |
| | ROOM 2407 RISERS | 5 |
| | ROOM 3407 RISERS | 6 |
| | ROOM 5233H RISERS | 7 |
| | ROOM 6109 RISERS | 8 |
| | ROOM 6407 RISERS | 8 |
| | ROOM 6233N RISERS | 9 |
| | WEST BUILDING ROOM B341 DOOR SCHEDULE | 1 |
| | WEST BUILDING ROOM B341 BATTERY CALCULATIONS | 2-3 |
| | WEST BUILDING ROOM B411 DOOR SCHEDULE | 4 |
| | WEST BUILDING ROOM B411 BATTERY CALCULATIONS | 5-6 |
| | WEST BUILDING ROOM 1409 DOOR SCHEDULE | 7 |
| | WEST BUILDING ROOM 1409 BATTERY CALCULATIONS | 8-9 |
| | WEST BUILDING ROOM 2407 DOOR SCHEDULE | 10 |
| | WEST BUILDING ROOM 2407 BATTERY CALCULATIONS | 11-13 |
| | WEST BUILDING ROOM 3407 DOOR SCHEDULE | 14 |
| | WEST BUILDING ROOM 3407 BATTERY CALCULATIONS | 15-16 |
| | WEST BUILDING ROOM 5233H DOOR SCHEDULE | 17 |
| | WEST BUILDING ROOM 5233H BATTERY CALCULATIONS | 18 |
| | WEST BUILDING ROOM 6109 DOOR SCHEDULE | 19 |
| | WEST BUILDING ROOM 6109 BATTERY CALCULATIONS | 20-22 |
| | WEST BUILDING ROOM 6407 DOOR SCHEDULE | 23 |
| | WEST BUILDING ROOM 6407 BATTERY CALCULATIONS | 24-25 |
| | WEST BUILDING ROOM 6233N DOOR SCHEDULE | 26 |
| | WEST BUILDING ROOM 6233N BATTERY CALCULATIONS | 27-28 |
| | WEST BUILDING EQUIPMENT LIST TOTAL COUNTS | 29 |


Use or disclosure of data on this sheet is subject to the restriction on the title page of this proposal.

TABLE OF CONTENTS ATTACHMENT 18 (APPENDIX I)
CUT SHEETS


| PART NUMBER | DESCRIPTION | MANUFACTURER | PAGE(S) |
|---|---|---|---|
| AL600ULPD4 | PACS Panel Power Supply | Altronix | 1-2 |
| AL1024ULACM | Power Supply | Altronix | 3-4 |
| BC400SG | Battery Enclosure, Grey Finish | Altronix | 5 |
| BT126 | Rechargeable Battery 12VDC 7AH | Altronix | 6 |
| BT1212 | Rechargeable Battery 12VDC 12AH | Altronix | 7 |
| MN-CAB3A+PSU-KIT | Symmetry CAB3A Enclosure Kit | AMAG | 8-13 |
| M2150-2DC | Symmetry M2150 2DC 2 Reader HSE Controller | AMAG | 8-13 |
| M2150-4DC | Symmetry M2150 4DC 4 Reader HSE Controller | AMAG | 8-13 |
| M2150-8DC | Symmetry M2150 8DC 8 Reader HSE Controller | AMAG | 8-13 |
| M2150-2DBC | Symmetry M2150 2DC 2 Reader HSE Controller | AMAG | 8-13 |
| M2150-4DBC | Symmetry M2150 4DC 4 Reader HSE Controller | AMAG | 8-13 |
| M2150-8DBC | Symmetry M2150 8DC 8 Reader HSE Controller | AMAG | 8-13 |
| WIM2 | Symmetry Wiegand Interface Module (WIM) 2 | AMAG | 8-13 |
| WIM4 | Symmetry Wiegand Interface Module (WIM) 4 | AMAG | 8-13 |
| WIM8 | Symmetry Wiegand Interface Module (WIM) 8 | AMAG | 8-13 |
| M2150-AC 8/4 | Symmetry M2150 8 Input/4 Output Module | AMAG | 8-13 |
| M2150-AC 24/4 | Alarm Controller | AMAG | 8-13 |
| M2150-OC 4/8 | Symmetry M2150 4 Input/4 Output Module | AMAG | 8-13 |
| NIC4 | Network Interface Card | AMAG | 8-13 |
| ENT/CLIENT-V7.0.1-HSE | Symmetry Enterprise HSE Administration Client Software | AMAG | 14-15 |
| ENT/128-CA-V7.0.1-HSE | Symmetry Enterprise HSE CLUSTER-AWARE | AMAG | 14-15 |
| XML-C&C-DEV-KIT-V7.0.1 | Symmetry XML Net Web Service to allow bi-directional data exchange | AMAG | 16-17 |
| THREAT-LEVEL-V7.0.1 | Symmetry Threat Level Manager | AMAG | 16-17 |
| Javelin S884 | Contactless Smart Card Reader | AMAG | 18-19 |
| DS150i | Request To Exit | BOSCH | 20-21 |
| Dell OptiPlex 990 | Dell OptiPlex 990 | DELL | 22-23 |
| 1078C | Door Position Switch | GE | 24-25 |
| 3040 | Duress Alarm Devices | GE | 26-27 |
| Hes 1006 | Electric Door Strike | Hess | 28-35 |
| RPK40 | HID iClass RPK40 | HID | 36-37 |
| RP40 | HID iClass RP40 | HID | 36-37 |
| FG1625 | Glass Break Detectors | Honeywell | 38-39 |
| DT-7550C | Dual Tech Motion Detector | Honeywell | 40-43 |
| L9080EU | L Series Commercial Locks | Marks | 44-45 |
| 1511 | EMLock 1500 Series Magnetic Lock | SDC | 46-47 |
| 423PU | Request To Exit Button | SDL | 48 |
| 2505AL | Surface Mount door contact | Sentrol | 49-50 |
| 2707A | Balance Magnetic Door Contact | Sentrol | 51-52 |
| DT6100STC | Glass Break Detectors | HONEYWELL | 53-54 |
| GUA-20G | 3/4 Flex Conduit | MAURICE | 55-56 |
| N/A | 3/4" Flex Coupling | MAURICE | 55-56 |
| RA-20G | 3/4" Flex Connector | MAURICE | 55-56 |
| HD-5200-1000 | Hard Drive | Pelco | 57-60 |
| ICS20CHV21 | Cameras | Pelco | 61-64 |
| NET5404T | Encoder | Pelco | 65-70 |
| SD435PG-E1 | Spectra PTZ Cameras | Pelco | 71-78 |


Use or disclosure of data on this sheet is subject to the restriction on the title page of this proposal.

TABLE OF CONTENTS ATTACHMENT 18 (APPENDIX I)
CUT SHEETS


| PART NUMBER | DESCRIPTION | MANUFACTURER | PAGE(S) |
|---|---|---|---|
| C10DN6R11A | Cameras | Pelco | 79-80 |
| RK5200PS-5U | Rack Mount Chassis with Power Supply | Pelco | 81-82 |
| 25221B | 22 AWG 2 Cond PVC Jacket 1000' rolls | ADI | 84 |
| 25270B | 22 AWG 6 Cond PVC Jacket 1000' rolls | ADI | 85 |
| 25244B | 18 AWG 4 Cond PVC jacket 1000' rolls | ADI | 86 |
| 25751B | 18 AWG 2 Cond PVC Jacket 1000' rolls | ADI | 87 |
| D2404 | 24 AWG 4 PR UTC (Cat 6) 1000' rolls | ADI | 94 |