Table 1
Summary of Soil & Groundwater Analytical Test Results for TPH Compounds
May 4, 2005

Former Western Scrap Site
Chicago Avenue and Industrial Highway
Gary, Indiana

				Analytical Results				
Sample Number	Sample Depth	PID Reading	Moisture (%)	TPH-DRO	TPH-GRO	TPH as Motor Oil	TPH-ERO	
		(PPM)		(mg/Kg)				
EXC 1-1	Floor -30"	0	30%	BDL	BDL	BDL	BDL	
EXC 1-2	Floor -28"	6.8	22%	BDL	BDL	250	250	
EXC 2-1	Wall -28"	177	8.5%	BDL	6,300	9,300	16,000	
EXC 2-2	Wall -36"	30	17%	BDL	280	870	1,150	
EXC 2-3	Wall -48"	369	13%	BDL	3,900	6,300	10,000	
EXC 2-4	Wall -48"	205	14%	BDL	11,000	23,000	34,000	
				mg/L				
EXC 2				BDL	250	270	520	
Soil Default Closure Levels				100	100	100	100	
Groundwater Default Closure Levels						1	1	

DCLs - Indiana Underground Storage Tank Branch Guidance Manual (1994)
TPH-DRO - Total Petroleum Hydrocarbons - Diesel Range Organics
TPH-GRO - Total Petroleum Hydrocarbons - Gasoline Range Organics
TPH-MO - Total Petroleum Hydrocarbons - Motor Oil
TPH-ERO - Total Petroleum Hydrocarbons - Extended Range Organics
Test results are based on a dry-weight basis
BDL - Below Detection Limits
NT - Not Tested
Note: Bold numbers indicate analytical test results are greater than the cleanup objective.