## NPS work Plan

1	
2	Removal of Disturbed Asbestos Containing Material
3	in the
4	Amphitheater Parking Lot
	•
5	in
6	Valley Forge National Historical Park
7	
8	
	SCOPE OF WORK: Provide all equipment, supplies and materials necessary to
	containerize, remove, and dispose of all asbestos containing materials (ACM) in the
	Southeast end of the Amphitheater Parking Lot that was disturbed by excavation
	(Approximately 15 to 30 tons. Weight will vary according to moisture content.) and
	remediate the site as required by these specifications.
14	
	SPECIFICATIONS:
	(1)As required by the OSHA Standards, a "Competent Person", as defined by 29
	CFR 1926.32 and 1926.1101, shall be designated by the Contractor to be in charge
	of the work performed on the site. For purposes of this contract, the Competent
	Person shall also be knowledgeable of 29 CFR 1910.120, 40 CFR 61 ,25 PCS 299, 25
	PCS 287 and Public Safety and have direct authority from the contractor to
	implement appropriate control measures in the event of a release of ACM into the
	environment, on site or during transportation of the material. The Competent
	Person shall have knowledge of asbestos, control strategies, and existing asbestos
	hazards and shall have direct authority from the contractor to implement or change
	strategies; and eliminate hazards. The Competent Person shall be on site while
	work is being performed and shall be available on an on-call basis after work hours
	should ACM containment or containers be breached, and shall have direct authority
	from the contractor to immediately respond with sufficient personnel and
	equipment to contain the material and prevent its release into the environment. The
	name of the Competent Person, along with contact phone numbers shall be provided
	to the Park Safety Specialist prior to work commencement.
32	
	(2)All asbestos containing material in the excavated spoil pile along the trench sides
	shall be containerized in a manner which prevents release, as required by 25 PCS
	299 and is suitable for disposal at a permitted disposal facility in compliance with 25
	PCS 287. The material shall be properly labeled in compliance with OSHA, EPA
	and State regulations, transported to a landfill permitted by the Pennsylvania
	Department of Environmental Protection (PADEP), and disposed of in compliance
	with all applicable Federal and State Regulations. The Contractor shall be
	responsible for submitting an original or certified copy to the Park of an Asbestos or
	Non-Hazardous Waste manifest from the permitted landfill where the ACM was
	interred. The manifest shall have the complete address of the receiving landfill; date
	& time of receipt; and description and weight of the material received. The
44	manifest shall be signed by an accepting official at the designated landfill.

46 (3) During the cleanup operation, transportation and interment of the material, the
47 Contractor shall be responsible for ensuring that there is no release of the material
48 into the environment in violation of 40 CFR 61 and 25 PCS 299. The area of the
49 spoil pile being worked and surrounding areas shall be saturated with water, or an
50 approved wetting agent, and the moving/working of all Asbestos Containing
51 Material (ACM) shall be done while the material is wet as defined by 29 CFR
52 1926.1101. Wetting agents containing surfactants or emulsifiers mixed with water
53 may be used to more effectively wet the ACM and surrounding areas. Technical
54 information and a Material Safety Data Sheet (MSDS) for the wetting agent must
55 be submitted to the Park Safety Specialist for approval prior to use.

57 (4) All ACM and ACM contaminated areas shall remain covered with a minimum 58 of 6 mil plastic sheeting or equivalent, and kept wet when not being worked by the 59 contractor. The sheeting shall be reasonably secured in a fashion that withstands 60 wind and other environmental problems. The area is currently plastic covered. 61 However, the contractor must have plastic sheeting on hand should the existing 62 sheeting deteriorate or be breached, and to cover additional areas of contamination.

64 (5) For the requirements of this contract, the Contractor shall be responsible for the 65 safety of the Public, and Public Safety shall be addressed in the Site Specific Safety 66 and Health Plan required by 29 CFR 1910.120. The Contractor shall designate a 67 Safety Zone sufficient in size to protect the public should there be a release of the 68 material, and provide all materials necessary to maintain a perimeter barrier to the 69 Public, Park Employees, and others not directly associated with contract work or 70 supervision. The Safety Zone perimeter shall be signed in English, informing others 71 of the specific hazard as specified in 29 CFR 1926.1101 and shall read:

## DANGER ASBESTOS CANCER AND LUNG DISEASE HAZARD AUTHORIZED PERSONNEL ONLY

78 (6)The Contractor shall be responsible for the safety of their employees, and any
79 subcontractor employees on the site, and shall comply with all required medical
80 monitoring, exposure assessments, air sampling, respiratory protection, personal
81 protective equipment, decontamination, and training, as well as other applicable
82 and mandatory provisions required by 29 CFR 1926.1101 and 29 CFR 1910.120. A
83 site specific Safety & Health Plan shall be submitted to and approved by the Park
84 Safety Specialist prior to any work being performed. The contractor shall be
85 responsible for insuring that all workers are properly trained; respirator fit tested;
86 and equipped in compliance with these standards and that all required medical
87 monitoring has been completed. All personal protective equipment; training
88 certificates; medical monitoring records; exposure assessments & monitoring;
89 respirator fit test documentation; and air sampling protocols shall be made available
90 to the Park Safety Specialist upon request.

92 (7)Original or Certified Copies of all air monitoring results shall be provided to the 93 Park as analytical proof that an airborne release of ACM has not occurred. Air 94 monitoring tests shall be reported in fiber(s) per cubic centimeter. Air monitoring 95 shall be performed as specified in 29 CFR 1926.1101 and 29 CFR 1926.1101 96 Appendix A.

97

98 (8)Decontamination wastes from personnel, tools, and equipment shall be treated as 99 ACM and shall be collected and containerized for disposal at the permitted landfill 100 in compliance with 40 CFR 61, 25 PCS 299 and 25 PCS 287. The contractor shall be 101 responsible for ensuring that there is not a release of decontamination waste into the 102 environment.

103

104 (9)Once the ACM has been removed, in compliance with 40 CFR 61.53, the
105 excavated trench containing fiber optics and copper cables, shall be backfilled and
106 compacted by the Contractor using a suitable asbestos free clean dirt/soil fill and the
107 surface adjacent to the trench shall be covered with a minimum of 6 (six) inches of
108 clean loosely compacted fill for a width of 6 (six) feet or as practical, to encapsulate
109 any ACM which may not have recovered for disposal. The contractor is responsible
110 for any settlement or erosion that is evident at the end of the warranty period. The
111 trench and surrounding surface area which may have been contaminated with ACM
112 shall be kept wet and plastic covered until the fill is in place. If fill material is
113 unsuitable to support grass growth, top soil shall be added to a depth of 4 inches
114 over the entire fill area.

115

116 (10) The fill area shall be broadcast seeded using a mixture of grass seed that is
117 suitable to the climate and the area, such as the mixture specified by the
118 Pennsylvania State Department of Transportation for grass seeding. The contractor
119 is responsible for grass cover, as required by 40 CFR 61.53, on all disturbed areas at
120 the end of the contract warranty.

121

122 (11) Care must be taken by the contractor not to damage or disturb the existing un123 covered fiber optics cable in the trench excavation during ACM cleanup, removal,
124 or fill remediation activities. Because the cable is lying on and surrounded by ACM,
125 contractor caused damage to the cable will be the responsibility of the contractor to
126 repair. Repair personnel shall be subject to the same OSHA worker protection
127 standards as the site workers as previously addressed.

128

129 (12)Because there appears to be an undetermined amount of undisturbed ACM
130 buried under the work site, at an unknown depth, no digging will be permitted
131 anywhere in the quarry area and the contractor shall use extreme care not to
132 disturb any buried ACM at the site. Should any of this buried ACM be disturbed
133 by the contractor, the contractor shall immediately halt the activity causing the
134 disturbance, implement wet measures to prevent a release, and immediately notify
135 the Park Safety Specialist.

136

137

138

139	<b>APPLICABLE FEDERAL AND STATE REGULATIONS:</b>
140	A. U.S. Department of Labor - Occupational Safety & Health
141	Administration (OSHA)
142	29 CFR 1926.1101 - Asbestos
143	29 CFR 1926.1101 Appendix A - Sampling & Analytical
144	
145	29 CFR 1926.1101 Appendix C - Qualitative and Quantitative
146	_ <del></del>
147	29 CFR 1926.1101 Appendix E - Interpretation and
148	Classification of Chest Roentgenograms
149	29 CFR 1910.120 - Hazardous Waste Operations and
150	Emergency Response
151	29 CFR 1910.120 Appendix B - Protection Levels and Levels of
152	Protective Gear
153	29 CFR 1910.120 Appendix C - Compliance Guidelines
154	
155	B. U.S. Environmental Protection Agency (EPA)
156	40 CFR 61 (M) - National Environmental Standards for
157	Hazardous Air Pollutants
158	
159	C. Commonwealth of Pennsylvania (PADEP)
160	Title 25 Pennsylvania Consolidated Statutes, Chpt. 287
161	Title 25 Pennsylvania Consolidated Statutes, Chpt. 299
162	Title 25 Pennsylvania Consolidated Statutes, Chpt. 125
163	
164	The Contractor shall be responsible for complying with all applicable and
165	mandatory provisions of the regulations listed above.
166	
	SUBMITTALS:
	Prior to initiating work, the contractor shall provide the following items to the Park
	for review and approval:
	Name, qualifications, and contact phone number(s) for the Contractor's
171	
172	
173	· • • • • • • • • • • • • • • • • • • •
174	
175	
176 177	
178	
179	
180	
181	
182	•
183	
184	
185	•
103	

186	Fill/top soil methods	of appl	ication and	d seeding method	to be used.			
187								
188								
189	Prior to disposal of ACM:							
190	Certified Empty wei	ight of t	ruck(s) and	d containers (if lin	ed dumpster is used).			
191								
192	Post Disposal of ACM:							
193	Non-hazardous Was	ste or As	bestos Ma	nifest from permi	tted landfill.			
194				-				
195	Air monitoring resu	lts.						
196	_							
197	Certified weight tick	kets for o	clean fill ar	nd or top soil.				
198	C			•				
199	NOTE: The Contracting C	)fficer re	eserves the	right to require s	ubmittals in addition			
	those called for in the speci			•				
201	-							
202	2 PRECONSTRUCTION CONFERENCE: A preconstruction meeting shall be held							
	3 at the Park to discuss contract provisions and specifications prior to work							
	commencement. The Contractor's "Competent Person" shall attend the							
205	5 preconstruction conference.							
206								
207	<b>SITE INSPECTIONS:</b> The	e Park S	afety Spec	ialist shall serve a	s the Contracting			
	Officer's Technical Represe				C			
	shall conduct periodic inspe				-			
	independent air monitoring			- ·	•			
	providing decontamination	_			-			
	2 facilities as required by the OSHA Standards. Prior to entry the Competent Person							
213	shall brief the Safety Specia	alist on s	ite proced	ures and site safet	y. The PADEP On			
	Scene Coordinator may wis		-		•			
	activities as well, and shall			_				
216								
217	<b>WORK COMPLETION C</b>	ERTIFI	CATION:	PADEP may wis	h to have an On			
218	Scene Coordinator review	the air s	ampling da	ata, disposal docu	mentation and certify			
	remediation. Should the O							
220	Specialist shall certify work	comple	tion as to	contract specificat	ions.			
221		_		_				
222	<b>BID SCHEDULE</b> :	Unit P	rice	Total				
223								
224	Mobilization			\$	_			
225	(planning , preparat	ion,			_			
226								
227								
228	Containerization	<b>\$</b>	per ton	\$				
229	(placing ACM in				_			
230	containers which							
231	prevents release & is	S						
232	acceptable to per-							

233	mitted landfill)			
234				
235	Disposal	\$	_ per ton	<b>\$</b>
236	(transportation &			
237	disposal of ACM)			
238				
239	Remediation (estim	nated 35	tons of top s	oil and /or clean fill)
240	Clean fill	\$	per ton	\$
241	Top soil	\$	per ton	\$
242	Seeding			\$
243				
244				